



CURB FACE ELEVATION

CONSTRUCTION NOTES:

- Strike control joints every 4'-0" and place expansion joints every 16'-0".
- 2. Install 1/2" preformed expansion joint material at all expansion joints and where sidewalk abuts concrete curb, foundations, aprons, or other concrete structures.
- All concrete construction shown on these standard details shall use 3000 P.S.I. SHA Mix No. 2 concrete unless otherwise specified.
- 4. All storm drain structures shall be underlain with a minimum 6" clean crushed stone base.

APPROVED: DIRECTOR DATE No. REVISIONS DATE

CITY OF WESTMINSTER DEPARTMENT OF PUBLIC WORKS

STANDARDS FOR SIDEWALK & ENTRANCE CONTRUCTION

ENTRANCE RECONSTRUCTION